BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT48589

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2021-22, Date: 01.10.2021

Name of Work:Pot Hole Filling to Roads in Ward No. 11 Kuvempunagara, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Chethan P ( )	
				In Figures	In Words
1	427.85	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406	Cum	2001.0	Rupees Two Thousand One Only
2	2852.31	KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications MORTH Specification No. 3004.2	Sqm	325.0	Rupees Three Hundred Twenty Five Only

chethan.P

Signature of the Contractor

3/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

3/03